# GRAMMAR

**LOCALITY MAP** 

# LILY STREET **BENDIGO**

**GB5116** 

## FOOTPATH RENEWAL **FEBRUARY 2024**



	DOCUMENT CON	NTROL		
SHEET No.	SHEET DESCRIPTION.	8/2/24	X/X/23	xx/x/23
		DRAFT	TENDER	CONSTRUCTION
		REVISION	REVISION	REVISION
1	COVER SHEET	Α	-	-
2	GENERAL NOTES & TYPICAL SECTION	Α	-	-
3 - 5	LAYOUT PLAN & LONG SECTION	Α	-	-
6 - 8	CROSS SECTIONS	Α	-	-
9	SETOUT	Α	-	-



## PROJECT EXTENTS

	INCOLO	1 E/MANAGO NE QUINEMENTO	
Item	Required	Comments	Contractor
Vegetation	Yes	Contact Arborist prior to works	
RRV	No	-	
CMA	No	-	
Planning Permit	No	-	
Land Acquisition	No	-	
CHMP	No	-	
Other	No		



	Draft Checked Tender Approved	A. SMITH N. SARTORI	X/X/23 X/X/23
2	PKELII	NINAKT DE: DRAFT 2.1	DIUN

PROJECT TITLE LILY STREET Location: **BENDIGO** Suburb: **FOOTPATH RENEWAL** Works: GB5116

Reference:

		Sheet:	1	of <b>9</b>	
(	COVER SHEET	Scale: -			A3
		Plot Date:08/	02/20	024 By:Leiç	gh Oliver
	AMENDMEN <sup>*</sup>	TS			
ision	Description		Apı	proved by	Date
	-			-	-

SHEET DETAILS

## **CONSTRUCTION SPECIFICATIONS**

All construction undertaken by, or on behalf of, The City of Greater Bendigo (CoGB) shall be undertaken in accordance with all DTP/Vicroads 200-700 series of Standard Specifications.

Compliance with the specifications to the satisfaction of the project Superintendent is required before a project can meet Practical Completion.

Sections of the DTP/Vicroads 200-700 series of standard specifications which are of particular relevance for this project include:

## **FORMATION**

201 Site Clearing

204 Farthworks

205 Rock Fill

210 Geotextiles in Earthworks

## FLEXIBLE PAVEMENTS

304 Unbound Flexible Pavement Construction

306 Cementitious Treated Pavement Subbase

307 In Situ Stabilisation of Pavements with Cementitious Binders

308 In Situ Stabilisation of Pavements with Foamed Bitumen Binder

310 Preparation of Granular Pavements for Bituminous Surfacing

## ASPHALT AND SURFACE TREATMENTS

402 Removal of Pavement by Cold Planing (profiling)

407 Dense Graded Asphalt

408 Sprayed Bituminous Surfacings

431 Coloured Surface Treatments

## **INCIDENTAL CONSTRUCTION**

701 Underground Stormwater Drains

702 Subsurface Drainage

703 General Concrete Paving704 Precast Concrete Kerb

705 Drainage Pits and Covers

706 Installation or Replacement of Utility Infrastructure within Road Reserves

707 Fencing

710 Fixing Raised Pavement Markers

712 Block Paving

713 Beaching

714 Sign Installation

721 Pavement Markings

731 Road Lighting Installation

## **MATERIAL SPECIFICATIONS**

## FOR WORKS DEPARTMENT

All materials used in construction projects undertaken by the CoGB Works department shall be compliant with the specifications setout in the relevant CoGB material panel supply contract.

Where panel supply contract information is not available, material specifications shall be sought from and supplied by the CoGB Engineering Department, and all materials used in construction must comply with those specifications.

## FOR EXTERNAL CONSULTANTS (inc. consultants engaged by the Works Dept.)

All materials used by external contractors engaged to undertake CoGB construction projects, or components thereof, shall be as per the material specification supplied within the instrument of engagement (Quote, Tender or Contract), or as per written instruction from the project Superintendents.

## PROJECT PLANNING REQUIREMENTS

## Permits and approvals

- Project permits and approvals which were required to be obtained prior to construction are listed in the below table
- Construction activities must be compliant with all conditions within the listed permits and approvals.

	PROJECT	PLANNING REQUIREMENTS	
Item	Required	Comments	Contractor
Vegetation	Yes	Contact Arborist prior to works	
RRV	No	-	
CMA	No	-	
Planning Permit	No	-	
Land Acquisition	No	-	
СНМР	No	-	
Other	No	-	

## **GENERAL NOTES**

## STANDARD DRAWINGS

Standard Drawings that are referenced within the design drawings are noted as 'SD', and are sourced from 3 locations. They are available for download online or from the project superintendent:

- 'CoGB SD' are sourced from the City of Greater Bendigo
   https://www.bendigo.vic.gov.au/Services/Roads-and-Drainage/Roads/Construction-standards
- 'IDM SD' are sourced from the Infrastructure Design Manual
- https://www.designmanual.com.au/
- 3. 'Vicroads SD' are sourced from Vicroads

https://www.vicroads.vic.gov.au/business-and-industry/technical-publications/technical-drawings-for-roadworks/standard-drawings-for-roadworks

## SERVICES SHOWN ON PLANS AND DURING CONSTRUCTION

- The location of underground services shown on design drawings have been derived from available information. Accuracy can not be guaranteed and should therefore be treated as indicative only.
- Gas and water property services are not located or shown on design drawings. It is the contractors responsibility to locate and alter these services as required to achieve the project design.
- Prior to undertaking construction activities, exact service locations must be arranged and marked onsite.
- The contractor will be held responsible for any damage caused to services.
- All service pit lids or valve covers within the works area are to be raised or lowered to match the design surface level to the relevant authority standards, unless noted otherwise on the construction plans, or by approval from the superintendent.
- Any service authority marker post found within the works area is to be relocated adjacent to their current position to a point 150mm offset from the nearest property boundary.
- Any PSM covers affected during works are to be renewed to CoGB SD293 unless noted otherwise, or by approval from the superintendent.

## DRAINAGE

 Any private storm water pipes discovered during works are to be plumbed to the nearest CoGB drainage pit, or with approval from the superintendent, to the nearest kerb or pipe

**CONSTRUCTION MANAGEMENT GUIDANCE** 

## OCCUPATIONAL HEALTH AND SAFETY

Delivery units shall consider appropriate management of occupational health and safety, and develop management plans compliant with ISO45001, and the City of Greater Bendigo integrated management system prior to any works beginning onsite


## SITE ENVIRONMENTAL MANAGEMENT PLAN

A Site Environmental Management Plan (SEMP) is to be developed by delivery units to manage the project site during the project delivery window. Consideration shall be given to appropriate management of the following, with a SEMP plan filled out and displayed onsite at all times:

- Communication and induction for staff, contractors and sub contractors
- Communication with appropriate adjacent residents/businesses
- Noise and Vibration
- Dust and contamination
- Chemicals
- Erosion and sediment
- wasie
- Vehicle and roadside management
- Vegetation, with particular focus on any relevant permit conditions and AS4970
- Heritage, with particular focus on any relevant permit conditions

## TRAFFIC MANAGEMENT PLAN

Where appropriate and prior to any works starting on site, delivery units must organise a AS1742.3 compliant traffic management plan, and have it approved by the relevant road authority.



Optional concrete
driveway construction
between footpath & kerb.
Requires landowner
signed agreement.



he location of underground services have been derived from valiable information, however accuracy cannot be guaranteed, lexisting service information should therefore be treated as dicative only, and service locations must be arranged prior to ommencement of any excavation. The contractor will be held sponsible for any damage caused to underground services.



PR	OJECT DESIGN ST	TATUS	ı
Surveyor	H. WHYTOCK	MAY. 2023	Г
Designer	L. OLIVER	DEC. 2023	ı
Draft Checked	A. SMITH	X/X/23	ı
Tender Approved	N. SARTORI	X/X/23	1
			ı

PRELIMINARY DESIGN DRAFT 2.1

Works:

Reference:

PROJECT TITLE

Location: LILY STREET

Suburb: BENDIGO

FOOTPATH RENEWAL

GB5116


GENERAL NOTES & TYPICAL SECTION


| Sheet: 2 OF 9 | Scale: - | A: | Plot Date:08/02/2024 | By:Leigh Olive


AMENDMENTS


Description Approved by Date
- - -


SHEET DETAILS


















Surveyor	H. WHYTOCK	MAY. 202
Designer	L. OLIVER	DEC. 202
Draft Checked	A. SMITH	X/X/23
Tender Approved	N. SARTORI	X/X/23

PRELIMINARY DESIGN | Works: **DRAFT 2.1** 

BENDIGO Suburb:

FOOTPATH RENEWAL GB5116 Reference:

SHEET DETAILS Sheet: 9 OF 9 SETOUT Scale: 1:250

AMENDMENTS