
# ARNOLD STREET, NORTH BENDIGO

GB5081
FOOTPATH
JUNE 2023





## PROJECT EXTENTS

APPROVAL TO CONSTRUCT STAMP	PROJECT PLANNING REQUIREMENTS			
	Item	Required	Comments	Contractor
	Vegetation	Yes	Arborist to assess	
	RRV	Yes	Comment only	
	CMA	No	-	
	Planning Permit	No	-	
	Land Acquisition	No	-	
	CHMP	No	-	
	PTV	Yes	Approval for bus stop relocation	



Surveyor:	H. WHYTOCK	21/03/2023
Designer:	A. SMITH	02/06/2023
Draft Checked:	L. OLIVER	xx/xx/2023
Tender Approved:	N. SARTORI	xx/xx/2023

**DRAFT 2** 

Location:	Arnold Street
Suburb:	North Bendigo
Works:	Footpath
GB No:	GB5081

PROJECT DETAILS

		Sheet number	er: 1	of 6
COVER SHEET		Plan Scale:	-	A3
		Plotted: 20/06/2	2023 By:Andr	rew Smith
	REVISIONS AFTER TENDER Description		Approved by	Date
-	-		-	-
-	-		-	-
-	-		-	-

SHEET DETAILS

DRAFT TENDER CONSTRUCTIO

GENERAL NOTES

DETAIL LAYOUT & LONG SECTION

DETAIL LAYOUT & LONG SECTION

#### **CONSTRUCTION SPECIFICATIONS**

All construction undertaken by, or on behalf of, The City of Greater Bendigo (CoGB) shall be undertaken in accordance with all DTP/Vicroads 200-700 series of Standard Specifications.

Compliance with the specifications to the satisfaction of the project Superintendent is required before a project can meet Practical Completion.

Sections of the DTP/Vicroads 200-700 series of standard specifications which are of particular relevance for this project include:

#### **FORMATION**

201 Site Clearing

204 Farthworks

205 Rock Fill

#### FLEXIBLE PAVEMENTS

304 Unbound Flexible Pavement Construction

310 Preparation of Granular Pavements for Bituminous Surfacing

#### ASPHALT AND SURFACE TREATMENTS

407 Dense Graded Asphalt

#### INCIDENTAL CONSTRUCTION

701 Underground Stormwater Drains

703 General Concrete Paving

705 Drainage Pits and Covers

714 Sign Installation

721 Pavement Markings

#### **MATERIAL SPECIFICATIONS**

#### FOR WORKS DEPARTMENT

All materials used in construction projects undertaken by the CoGB Works department shall be compliant with the specifications setout in the relevant CoGB material panel supply contract.

Where panel supply contract information is not available, material specifications shall be sought from and supplied by the CoGB Engineering Department, and all materials used in construction must comply with those specifications.

#### FOR EXTERNAL CONSULTANTS (inc. consultants engaged by the Works Dept.)

All materials used by external contractors engaged to undertake CoGB construction projects, or components thereof, shall be as per the material specification supplied within the instrument of engagement (Quote, Tender or Contract), or as per written instruction from the project Superintendents.

#### PROJECT PLANNING REQUIREMENTS

#### Permits and approvals

- Project permits and approvals which were required to be obtained prior to construction are listed in the below table
- Construction activities must be compliant with all conditions within the listed permits and approvals.

PROJECT PLANNING REQUIREMENTS			
Item	Required	Comments	Contractor
Vegetation	Yes	Arborist to assess	
RRV	Yes	Comment only	
CMA	No	-	
Planning Permit	No	-	
Land Acquisition	No	-	
CHMP	No	-	
PTV	Yes	Approval for bus stop relocation	

### **GENERAL NOTES**

#### STANDARD DRAWINGS

Standard Drawings that are referenced within the design drawings are noted as 'SD', and are sourced from 3 locations. They are available for download online or from the project superintendent:

- 'CoGB SD' are sourced from the City of Greater Bendigo
   https://www.bendigo.vic.gov.au/Services/Roads-and-Drainage/Roads/Construction-standards
- 'IDM SD' are sourced from the Infrastructure Design Manual
- https://www.designmanual.com.au/
- 3. 'Vicroads SD' are sourced from Vicroads

https://www.vicroads.vic.gov.au/business-and-industry/technical-publications/technical-drawings-for-roadworks/standard-drawings-for-roadworks

#### SERVICES SHOWN ON PLANS AND DURING CONSTRUCTION

- The location of underground services shown on design drawings have been derived from available information. Accuracy can not be guaranteed and should therefore be treated as indicative only.
- Gas and water property services are not located or shown on design drawings. It is the contractors responsibility to locate and alter these services as required to achieve the project design.
- Prior to undertaking construction activities, exact service locations must be arranged and marked onsite.
- The contractor will be held responsible for any damage caused to services.
- All service pit lids or valve covers within the works area are to be raised or lowered to match the design surface level to the relevant authority standards, unless noted otherwise on the construction plans, or by approval from the superintendent.
- Any service authority marker post found within the works area is to be relocated adjacent to their current position to a point 150mm offset from the nearest property boundary.
- Any PSM covers affected during works are to be renewed to CoGB SD293 unless noted otherwise, or by approval from the superintendent.

#### DRAINAGE

 Any private storm water pipes discovered during works are to be plumbed to the nearest CoGB drainage pit, or with approval from the superintendent, to the nearest kerb or pipe

**CONSTRUCTION MANAGEMENT GUIDANCE** 

#### OCCUPATIONAL HEALTH AND SAFETY

Delivery units shall consider appropriate management of occupational health and safety, and develop management plans compliant with ISO45001, and the City of Greater Bendigo integrated management system prior to any works beginning


#### SITE ENVIRONMENTAL MANAGEMENT PLAN

A Site Environmental Management Plan (SEMP) is to be developed by delivery units to manage the project site during the project delivery window. Consideration shall be given to appropriate management of the following, with a SEMP plan filled out and displayed onsite at all times:

- Communication and induction for staff, contractors and sub contractors
- Communication with appropriate adjacent residents/businesses
- Noise and Vibration
- Dust and contamination
- Chemicals
- Frosion and sediment
- Waste
- Vehicle and roadside management
- Vegetation, with particular focus on any relevant permit conditions and AS4970
- Heritage, with particular focus on any relevant permit conditions

#### TRAFFIC MANAGEMENT PLAN

Where appropriate and prior to any works starting on site, delivery units must organise a AS1742.3 compliant traffic management plan, and have it approved by the relevant road authority.





DRAFT 2


Location: Arnold Street
Suburb: North Bendigo
Works: Footpath


GB No:


GB5081


PROJECT DETAILS

SHEET DETAILS









EXISTING PIPE TO REMAIN

DESIGN PIPE / PIT or ENDWALL

LEGEND

CoGB SD390 TRENCH BACKFILL (BEHIND KERB)

CoGB SD391 TRENCH BACKFILL (UNDER NEW ROAD)

CoGB SD392 TRENCH BACKFILL (UNDER EXISTING ROAD)





PROJECT DETAILS			SHEET DETAILS		
	A		SETOUT &	Sheet nu	
	Location: Arnold Street		DRAINAGE	Plan Sca	
	Suburb:	North Bendigo		DIVAIIVAGE	Plotted: 20
		ŭ		REVISIONS AFTER TENDER Description	
	Works:	Footpath	-	-	
	GB No:	GB5081	-	-	
	CD . 10.	000001			

Sheet number: 6 of 6

A3

Plan Scale: 1:500